

MODEL : HRP-150-5

## OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1 : 80 mVp-p (Max)	I/P : 230VAC O/P : FULL LOAD Ta : 25°C	V1 : 10 mVp-p (Max)	P
2	OUTPUT VOLTAGE ADJUST RANGE	CH1 : 4.3 V ~ 5.8 V	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	4.121 V~ 6.27 V / 230 VAC 4.121 V~ 6.269 V / 115 VAC	P
3	OUTPUT VOLTAGE TOLERANCE	V1 : 2.5 %~ -2.5 % (Max)	I/P : 100 VAC / 264 VAC O/P : FULL / MIN LOAD Ta : 25°C	V1 : 0.35 %~ -0.35 %	P
4	LINE REGULATION	V1 : 0.5 %~ -0.5 % (Max)	I/P : 100VAC ~ 264 VAC O/P : FULL LOAD Ta : 25°C	V1 : 0 %~ 0 %	P
5	LOAD REGULATION	V1 : 1 %~ -1 % (Max)	I/P : 230 VAC O/P : FULL ~MIN LOAD Ta : 25°C	V1 : 0.25 %~ -0.25 %	P
6	SET UP TIME	230VAC : 3000 ms (Max) 115 VAC : 3000 ms (Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 1208 ms 115VAC/ 1208 ms	P
7	RISE TIME	230VAC : 50 ms (Max) 115VAC : 50 ms (Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 6 ms 115VAC/ 6 ms	P
8	HOLD UP TIME	230VAC : 16 ms (TYP) 115VAC : 16 ms (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 29 ms 115VAC/ 26 ms	P
9	OVER/UNDERSHOOT TEST	< ±5%	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	TEST : < 5 %	P
10	DYNAMIC LOAD	V1 : 1000 mVp-p	I/P : 230 VAC O/P : FULL /Min LOAD 90%DUTY/1KHZ Ta : 25°C	404 mVp-p	P

## INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	85VAC~264 VAC	I/P : TESTING O/P : FULL LOAD Ta : 25°C	65 V~264V	P
			I/P : LOW-LINE-3V= 97 V HIGH-LINE+15%=300 V O/P : FULL/MIN LOAD ON : 30 Sec . OFF : 30 Sec 10MIN ( AC POWER ON/OFF NO DAMAGE )	TEST : OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P : 100 VAC ~ 264 VAC O/P : FULL-MIN LOAD Ta : 25°C	TEST : OK	P
3	POWER FACTOR	0.95 / 230 VAC(TYP) 0.99 / 115 VAC(TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	PF= 0.971 / 230 VAC PF= 1 / 115 VAC	P
4	EFFICIENCY	85% (TYP)	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	86.8 %	P
5	INPUT CURRENT	230V/ 1.3 A (TYP) 115V/ 2.3 A (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I = 0.685 A/ 230 VAC I = 1.382 A/ 115 VAC	P
6	INRUSH CURRENT	230V/ 70 A (TYP) 115V/ 35 A (TYP) COLD START	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I = 70 A/ 230 VAC I = 35 A/ 115 VAC	P
7	LEAKAGE CURRENT	< 1 mA / 240 VAC	I/P : 264 VAC O/P : Min LOAD Ta : 25°C	L-FG : 0.28 mA N-FG : 0.72 mA	P

### PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	105%~135%	I/P : 230 VAC I/P : 115 VAC O/P : TESTING Ta : 25°C	119% / 230 VAC 119% / 115 VAC Constant Current Limiting	P
2	OVER VOLTAGE PROTECTION	CH1 : 6V~7V	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	6.47 V / 230 VAC 6.47 V / 115 VAC Shut down Re- power ON	P
3	OVER TEMPERATURE PROTECTION	SPEC : TSW1 : 95 ± 5°C O.T.P. TSW2 : 105 ± 5°C O.T.P. NO DAMAGE	I/P : 230 VAC O/P : FULL LOAD	O.T.P. Active Shut down o/p voltage , recovers automatically after temperature goes down	P
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P : 264 VAC O/P : FULL LOAD Ta : 25°C	NO DAMAGE Constant Current Limiting	P

### CONTROL FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	REMOTE SENSE	>0.3V	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	>0.3V	P

### ENVIRONMENT TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT		
1	TEMPERATURE RISE TEST	MODEL : HRP-150-5			P		
		1. ROOM AMBIENT BURN-IN : 2 HRS I/P : 230VAC O/P : FULL LOAD Ta=31.8 °C					
		2. HIGH AMBIENT BURN-IN : 2 HRS I/P : 230VAC O/P : FULL LOAD Ta=47.9 °C					
		2	OVER LOAD BURN-IN TEST	NO DAMAGE 1 HOUR ( MIN )		I/P : 230 VAC O/P : 110 % LOAD Ta : 25°C	TEST : OK
3	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P : 230 VAC O/P : 100 % LOAD Ta= -40 °C	TEST : OK	P		
4	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 40 °C NO DAMAGE	I/P : 272 VAC O/P : FULL LOAD Ta= 40 °C HUMIDITY= 95 %R.H	TEST : OK	P		
5	TEMPERATURE COEFFICIENT	± 0.04 % (0~50°C)	I/P : 230 VAC O/P : FULL LOAD	± 0.014 % (0~50°C)	P		
6	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10~500Hz (3) Sweep Time : 10min/sweep cycle (4) Acceleration : 5G (5) Test Time : 1 hour in each axis (X.Y.Z) (6) Ta : 25°C		TEST : OK	P		

### SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P : 3 KVAC/min I/P-FG : 2 KVAC/min O/P-FG : 0.5 KVAC/min	I/P-O/P : 3.6 KVAC/min I/P-FG : 2.4 KVAC/min O/P-FG : 0.6 KVAC/min Ta : 25°C	I/P-O/P : 3.56 mA I/P-FG : 2.815 mA O/P-FG : 2.043 mA NO DAMAGE 30	P
2	ISOLATION RESISTANCE	I/P-O/P : 500VDC>100MΩ I/P-FG : 500VDC>100MΩ O/P-FG : 500VDC>100MΩ	I/P-O/P : 500 VDC I/P-FG : 500 VDC O/P-FG : 500 VDC Ta : 25°C /70%RH	I/P-O/P : 30 GΩ I/P-FG : 30 GΩ O/P-FG : 30 GΩ NO DAMAGE	P
3	GROUNDING CONTINUITY	FG(PE) TO CHASSIS OR TRACE < 100 mΩ	40 A / 2min Ta : 25°C / 70%RH	2 mΩ	P
4	APPROVAL	TUV : Certificate NO : R50147701 UL : File NO : E183223			P

### E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2,-3 CLASS A	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	PASS	P
2	CONDUCTION	EN55022 CLASS B	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	PASS Test by certified Lab	P
3	RADIATION	EN55022 CLASS B	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	PASS Test by certified Lab	P
4	E.S.D	EN61000-4-2 INDUSTRY AIR : 8KV / Contact : 4KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
5	E.F.T	EN61000-4-4 INDUSTRY INPUT : 2KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
6	SURGE	IEC61000-4-5 INDUSTRY L-N : 2KV L,N-PE : 4KV	I/P : 230 VAC/50HZ O/P : FULL LOAD Ta : 25°C	CRITERIA A	P
7	Test by certified Lab & Test Report Prepare				

### M.T.B.F & LIFE CYCLE CALCULATION

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	CAPACITOR LIFE CYCLE	HRP-150-5 : SUPPOSE C105 IS THE MOST CRITICAL COMPONENT I/P : 230VAC O/P : FULL LOAD Ta= 25 °C LIFE TIME= 157781 HRS I/P : 230VAC O/P : FULL LOAD Ta= 40 °C LIFE TIME= 49602 HRS			P
2	MTBF	MIL-HDBK-217F NOTICES2 PARTS COUNT TOTAL FAILURE RATE : 238.8K HRS			P
3	DMTBF/Accelerated Life Test	Demonstration Mean Time Between Failure : Above 50,000 hours @ TA 40°C			P

COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor ( D to S) or (C to E) Peak Voltage	Q 3 Rated 2SK4106 12A/500V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2) Output Short Ta : 25°C	(1) 436 V (2) 426 V	P
2	Diode Peak Voltage	Q101 Rated STP80NF03L-04 80A/30V  Q103 Rated IRL3103PbF 64A/30V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2)Output Short O/P : (1)Full Load Turn on (2)Output Short Ta : 25°C	(1) 24.4 V (2) 22.6 V  (1) 23.8 V (2) 23.8 V	P
3	PFC Transistor ( D to S) or (C to E) Peak Voltage	Q1 Rated : IRFP460A 20A/500V	I/P : High-Line +3V = 267 V O/P : (1)Full Load (2) Dynamic Load 90%Duty/1KHz Ta : 25°C	(1) 440 V (2) 438 V	P
4	Input Capacitor Voltage	C5 Rated 100u/400V 105°C KMG	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 376 V (2) 377.3 V (3) 377.3 V	P
5	Control IC Voltage Test	U 2 Rated FAN4801 : 12V~30V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 15.5 V (2) 15.5 V (3) 15.5 V	P

DATE	SAMPLE	TEST RESULT	TESTER	APPROVAL
2008/12/1	RD SAMPLE	PASS	SANFORD SU	VINCENT TSENG
2009/3/25	PRODUCT SAMPLE W0812D43	PASS	SANFORD SU	VINCENT TSENG
2009/6/16	PRODUCT SAMPLE W0905A31	PASS	SANFORD SU	VINCENT TSENG

2003/12/12 A50-F023